



Average Unit Cost Per Element for a Group of Projects

Cost Per Mile of Alignment (Average) (\$X000):	\$68,343
Selected Projects:	Charlotte - South Corridor LRT Denver - Southeast Corridor Project - T-Rex Denver - Southwest Corridor Los Angeles - East Side Extension Minneapolis - Hiawatha Corridor New Jersey - Newark Rail Link New Jersey - Southern NJ Light Rail Transit System Norfolk - Light Rail Transit Phoenix - Central Phoenix/East Valley Portland - Interstate MAX Portland - South Corridor/Portland Mall Sacramento - Folsom Corridor Sacramento - South Corridor Salt Lake City - Mid Jordan LRT Santa Clara VTA - Tasman West St. Louis - St. Clair County Extension
Cost Per Mile of Alignment (Minimum) (\$X000):	\$0
Cost Per Mile of Alignment (Maximum) (\$X000):	\$182,697
Miles of Alignment (Minimum):	5.75
Miles of Alignment (Maximum):	39.98
Amount is in Selected Base Year:	2016

Cost Category and Element	Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
10 Guideway & Track Elements	LF Guideway			\$4,203
10.010 Guideway: At-grade exclusive right-of-way	LF Guideway	12	57,850	\$2,101
10.020 Guideway: At-grade semi-exclusive (allows cross-traffic)	LF Guideway	7	27,301	\$2,277
10.030 Guideway: At-grade in mixed traffic	LF Guideway	4	9,768	\$3,353
10.040 Guideway: Aerial structure	LF Guideway	4	6,165	\$11,192
10.041 Bridges	LF Guideway	0	0	\$0
10.042 Viaduct	LF Guideway	0	0	\$0
10.043 Other Structure	LF Guideway	0	0	\$0



Average Unit Cost Per Element for a Group of Projects

Cost Category and Element		Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
10.044	Unspecified	LF Guideway	4	1,541	\$9,993
10.050	Guideway: Built-up fill	LF Guideway	3	5,095	\$4,089
10.060	Guideway: Underground cut & cover	LF Guideway	1	17,000	\$12,580
10.061	Cut & Cover Guideway Soft Soils	LF Guideway	0	0	\$0
10.062	Cut & Cover Guideway Hard Soils	LF Guideway	0	0	\$0
10.063	Cut & Cover Guideway Vent Soft Soils	LF Guideway	0	0	\$0
10.064	Cut & Cover Guideway Vent Hard Soils	LF Guideway	0	0	\$0
10.065	Unspecified	LF Guideway	1	17,000	\$12,580
10.070	Guideway: Underground tunnel	LF Guideway	1	8,976	\$33,878
10.071	Bored Earth Open	LF Guideway	0	0	\$0
10.072	Bored Earth Close	LF Guideway	0	0	\$0
10.073	Bored Earth Mixed Shield	LF Guideway	0	0	\$0
10.074	Bored Earth Mixes Shield SEM	LF Guideway	0	0	\$0
10.075	Rock Drill & Blast	LF Guideway	0	0	\$0
10.076	Rock Boring Machine	LF Guideway	0	0	\$0
10.077	Sunken Tunnel	LF Guideway	0	0	\$0
10.078	Unspecified	LF Guideway	0	0	\$0
10.080	Guideway: Retained cut or fill	LF Guideway	5	32,899	\$3,459
10.090	Track: Direct fixation	Track Feet	10	21,449	\$714
10.100	Track: Embedded	Track Feet	7	46,323	\$674
10.110	Track: Ballasted	Track Feet	11	91,815	\$340
10.120	Track: Special (switches, turnouts)	Track Feet	8	59,936	\$68,053
10.130	Track: Vibration & Noise Dampening	Track Feet	2	86,569	\$114
10.140	Special Structures	LF Guideway	1	147,878	\$708
20	Stations, Stops, Terminals, Intermodels	Stations			\$4,729,938
20.010	At-Grade Station, Stop, Shelter, Mall, Terminal, Platform	Stations	14	14	\$3,465,907
20.020	Aerial station, stop, shelter, mall, terminal, platform	Stations	0	0	\$0
20.030	Underground station, stop, shelter, mall, terminal, platform	Stations	1	1	\$42,325,165
20.031	Cut and Cover	Stations	0	0	\$0
20.032	Bored Earth Soft Soils	Stations	0	0	\$0
20.033	Bored Rock Hard Soils	Stations	0	0	\$0
20.034	Unspecified	Stations	1	1	\$33,922,639
20.040	Major stations, landings, terminals: Intermodal, ferry, trolley, etc.	Stations	2	2	\$792,414
20.050	Joint development	Stations	1	10	\$55,154
20.060	Automobile parking multi-story structure	Spaces	2	1,025	\$19,255
20.070	Elevators, escalators	Number	0	0	\$0

Cost Category and Element		Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
20.071	Elevators	Number	0	0	\$0
20.072	Escalators	Number	0	0	\$0
20.073	Unspecified	Number	0	0	\$0
20.080	Passenger Overpass	Number	3	2	\$1,709,983
20.090	Underground Interconnecting Tunnel	Number	0	0	\$0
20.091	Cut and Cover	Number	0	0	\$0
20.092	Bored Earth Soft Soils	Number	0	0	\$0
20.093	Bored Rock Hard Soils	Number	0	0	\$0
20.094	Unspecified	Number	0	0	\$0
20.100	Signage and Graphics	Stations	2	14	\$184,576
30	Support Facilities: Yards, Shops, Admin. Bldgs	LF Guideway			\$1,588,570
30.010	Administration Building: Office, sales, storage, revenue counting	LF Guideway	1	1,152,646	\$30
30.011	Administrative Building	LF Guideway	0	0	\$0
30.012	Central Control Facility	LF Guideway	1	147,878	\$106
30.013	Central Revenue Counting Facility	LF Guideway	0	0	\$0
30.014	Unspecified	LF Guideway	0	0	\$0
30.020	Light Maintenance Facility	Vehicles	4	4,380	\$291,547
30.030	Heavy Maintenance Facility	Vehicles	7	23,373	\$1,287,006
30.040	Storage or Maintenance of Way Building	LF Guideway	3	62,480	\$40
30.050	Yard and Yard Track	Track Feet	5	63,066	\$1,315,009
40	Sitework & Special Conditions	LF Guideway			\$1,459
40.010	Demolition, Clearing, Earthwork	LF Guideway	9	57,747	\$155
40.020	Site Utilities, Utility Relocation	LF Guideway	7	1,152,646	\$549
40.021	Urban Replacement In-Kind Public Utilities	LF Guideway	6	74,503	\$67
40.022	Urban Replacement In-Kind Private Utilities	LF Guideway	6	74,503	\$66
40.023	Urban Replacement Betterment Public Utilities	LF Guideway	1	147,878	\$39
40.024	Urban Replacement Betterment Private Utilities	LF Guideway	1	147,878	\$39
40.025	Suburban Replacement In-Kind Public Utilities	LF Guideway	7	69,488	\$111
40.026	Suburban Replacement In-Kind Private Utilities	LF Guideway	6	74,503	\$57
40.027	Suburban Replacement Betterment Public Utilities	LF Guideway	1	147,878	\$39
40.028	Suburban Replacement Betterment Private Utilities	LF Guideway	1	147,878	\$39
40.029	Unspecified	LF Guideway	0	0	\$0
40.030	Haz. mat'l, contam'd soil removal/mitigation, ground water treatments	LF Guideway	2	1,152,646	\$28
40.031	HazMat Abatement	LF Guideway	0	0	\$0
40.032	Contaminated Soil Removal	LF Guideway	0	0	\$0
40.033	Ground Water Treatment	LF Guideway	0	0	\$0
40.034	Unspecified	LF Guideway	2	61,116	\$20



Average Unit Cost Per Element for a Group of Projects

Cost Category and Element	Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
40.040 Environmental mitigation, e.g. wetlands, historic/archeologic, parks	LF Guideway	10	67,480	\$87
40.050 Site structures including retaining walls, sound walls	LF Guideway	5	0	\$210
40.051 Mechanically Stabilized Earth Walls	LF Guideway	0	0	\$0
40.052 Concrete Walls	LF Guideway	0	0	\$0
40.053 Other Walls	LF Guideway	0	0	\$0
40.054 Unspecified	LF Guideway	0	0	\$0
40.060 Pedestrian / bike access and accommodation, landscaping	LF Guideway	6	70,398	\$259
40.070 Automobile, bus, van accessways including roads, parking lots	Spaces	2	4,720	\$14,940
40.071 Surface Parking Lot	Spaces	2	2,360	\$7,567
40.072 Auto Access	Stations	0	0	\$0
40.073 Bus Access	Spaces	0	0	\$0
40.074 Bus Parking and Berthing	Spaces	0	0	\$0
40.075 Unspecified	Spaces	0	0	\$0
40.080 Temporary Facilities and other indirect costs during construction	LF Guideway	3	1,152,646	\$1,031
40.081 Roadway Changes	LF Guideway	3	82,103	\$102
40.082 Third-Party Work	LF Guideway	2	53,735	\$105
40.083 Mobilization	LF Guideway	1	68,070	\$21
40.084 Maintenance of Traffic	LF Guideway	0	0	\$0
40.085 Unallocated Indirect Costs	LF Guideway	0	0	\$0
40.086 Unspecified	LF Guideway	1	30,360	\$1,866
50 Systems	Track Feet			\$944
50.010 Train control and signals	Track Feet	7	1,548,719	\$318
50.011 Train Control - Wayside	Track Feet	7	131,021	\$319
50.012 Train Control - On Board Systems	Track Feet	1	95,262	\$5
50.013 Train Control - Centralized Systems	Track Feet	0	0	\$0
50.014 Unspecified	Track Feet	0	0	\$0
50.020 Traffic signals and crossing protection	Track Feet	7	131,372	\$165
50.030 Traction power supply: substations	Track Feet	13	119,614	\$156
50.040 Traction power distribution: catenary and third rail	Track Feet	6	1,548,719	\$258
50.041 Catenary	Track Feet	6	103,565	\$257
50.042 Third Rail	Track Feet	0	0	\$0
50.043 Power Distribution and Connections	Track Feet	1	66,528	\$45
50.044 Unspecified	Track Feet	1	74,250	\$228
50.050 Communications	Track Feet	6	1,548,719	\$176
50.051 Wired	Track Feet	0	0	\$0
50.052 Radio Based	Track Feet	0	0	\$0
50.053 Unspecified	Track Feet	6	138,721	\$146



Average Unit Cost Per Element for a Group of Projects

Cost Category and Element		Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
50.060	Fare collection system and equipment	Stations	7	200	\$277,689
50.061	Central Revenue Counting Systems	Stations	0	0	\$0
50.062	Revenue Collection - In Station	Stations	7	14	\$303,178
50.063	Revenue Collection - On Vehicle	Vehicles	0	0	\$0
50.064	Unspecified	Stations	1	28	\$70,146
50.070	Central Control System	LF Guideway	4	72,851	\$70
60	Row, Land, Existing Improvements	LF Guideway			\$1,010
60.010	Purchase or lease of real estate	LF Guideway	8	1,152,646	\$926
60.011	Full Takes	LF Guideway	0	0	\$0
60.012	Part Takes	LF Guideway	0	0	\$0
60.013	Easement Acquisitions	LF Guideway	0	0	\$0
60.014	Other Rights	LF Guideway	0	0	\$0
60.015	Donated Value	LF Guideway	0	0	\$0
60.016	Unspecified	LF Guideway	8	64,597	\$842
60.020	Relocation of existing households and businesses	LF Guideway	4	1,152,646	\$118
60.021	Residential (Owners)	LF Guideway	0	0	\$0
60.022	Residential (Tenants)	LF Guideway	0	0	\$0
60.023	Business (Owners and Tenants)	LF Guideway	0	0	\$0
60.024	Others (Personal Property Moves)	LF Guideway	0	0	\$0
60.025	Unspecified	LF Guideway	4	57,426	\$39
60.030	Services	LF Guideway	2	1,152,646	\$31
60.031	Property Management	LF Guideway	0	0	\$0
60.032	Agency	LF Guideway	2	50,667	\$11
60.033	Contractor R/W Services (Title/Appraisal, etc)	LF Guideway	2	79,971	\$28
60.034	Legal Services	LF Guideway	0	0	\$0
60.035	Unspecified	LF Guideway	1	39,400	\$60
60.040	Other Real Estate Costs	LF Guideway	2	38,184	\$1,031
70	Vehicles	Vehicles			\$5,139,784
70.010	Light Rail	Vehicles	6	160	\$5,098,119
70.011	Static	Vehicles	0	0	\$0
70.012	Articulated	Vehicles	2	17	\$5,151,807
70.013	Unspecified	Vehicles	6	21	\$5,239,587
70.020	Heavy Rail	Vehicles	0	0	\$0
70.021	Small Scale	Vehicles	0	0	\$0
70.022	Large Scale	Vehicles	0	0	\$0
70.023	Unspecified	Vehicles	0	0	\$0
70.030	Commuter Rail	Vehicles	0	0	\$0



Average Unit Cost Per Element for a Group of Projects

Cost Category and Element		Units	Number of Projects	Average Unit Quantity	Average Unit Cost in National Average User Selected Base Year 2016
70.031	Locomotive	Vehicles	0	0	\$0
70.032	Passenger Car	Vehicles	0	0	\$0
70.033	Bi-Level Passenger Car	Vehicles	0	0	\$0
70.034	Self-Propelled Passenger Car	Vehicles	0	0	\$0
70.035	Unspecified	Vehicles	0	0	\$0
70.040	Bus	Vehicles	0	0	\$0
70.041	Small Bus	Vehicles	0	0	\$0
70.042	Standard 40 Foot Bus	Vehicles	0	0	\$0
70.043	Articulated Bus	Vehicles	0	0	\$0
70.044	Unspecified	Vehicles	0	0	\$0
70.050	Other Vehicles	Vehicles	0	0	\$0
70.060	Non-revenue vehicles	Vehicles	1	329	\$76,933
70.061	Maintenance of Way Vehicles	Vehicles	1	24	\$131,142
70.062	Automobiles	Vehicles	0	0	\$0
70.063	Trucks	Vehicles	0	0	\$0
70.064	Unspecified	Vehicles	1	24	\$22,724
70.070	Spare parts/ Rotable Components	Vehicles	2	25	\$214,721
80	Professional Services	Hard Costs			
80.010	Preliminary Engineering	Hard Costs	6	5.43%	5.43%
80.020	Final Design	Hard Costs	15	13.82%	13.82%
80.030	Project Management for Design and Construction	Hard Costs	5	9.77%	9.77%
80.031	Agency Project Management	Hard Costs	5	8.85%	8.85%
80.032	Project Management Oversight Support	Hard Costs	2	0.70%	0.70%
80.033	Agency Force Account	Hard Costs	0	0.07%	0.07%
80.034	Unspecified	Hard Costs	1	15.82%	15.82%
80.040	Construction Administration & Management	Hard Costs	14	8.75%	8.75%
80.050	Professional Liability and other Non-Construction Insurance	Hard Costs	10	1.73%	1.73%
80.060	Legal; Permits; Review Fees by other agencies, cities, etc.	Hard Costs	5	2.08%	2.08%
80.070	Surveys, Testing, Investigation, Inspection	Hard Costs	5	3.06%	3.06%
80.080	Start up	Hard Costs	6	2.33%	2.33%
80.081	Training/Start-up	Hard Costs	0	0.00%	0.00%
80.082	Safety Certification	Hard Costs	1	0.31%	0.31%
80.083	Off-Site Vehicle Testing, Test Runs	Hard Costs	6	1.56%	1.56%
80.084	Commissioning	Hard Costs	0	0.00%	0.00%
80.085	Unspecified	Hard Costs	1	4.71%	4.71%
80.090	Other	Hard Costs	8	1.18%	1.18%